



SR 92 Section 750
Stone Masonry Arch Rehabilitation
ECMS #10229

2024 ACEC/PA Diamond Award Recipient – Category J: Small Projects

GPI



Chris Messner, PE

Project Manager / Assist. Vice President

cmessner@gpinet.com

570.880.7345




Bob Bochicchio, PE, DBIA

Project Manager / Senior Structural Engineer

rbochicchio@gpinet.com

570.880.7334

Project Overview / Constraints



Project Overview / Constraints



Project Overview / Constraints



Project Overview / Constraints



Project Overview / Constraints




Purpose:

The purpose of the project is to address structural deficiencies while preserving the life of the existing structure and to maintain a safe and efficient access over the roadway to serve local residents, emergency services, etc.

Need:

The project is needed due to structure condition. The existing culvert has stone wingwalls and a culvert with a timber supported base. The wingwalls' stonework has breaks running along the layers due to shifting. The timber base appears to have fractured and settled in multiple locations.


Environmental Conditions




Inspection March 2018 – Recommended Structure Work

- *Culvert Barrel – Priority 1*
 - 4” movement over 12 months at intrados.
- *Headwalls/Wingwalls – Priority 2*
 - Pushed, displaced, settled and/or missing stones at the inlet spandrel and wingwalls.
- *Scour – Priority 2*
 - Advanced scour threatens inlet headwall, wings, and barrel.
- *Debris – Priority 3*
 - Remove vegetated sediment buildup at the far right extending upstream.


Existing Conditions




Existing Conditions



LGTS / Moment Slab with Toe Wall




SR 0092
TYPICAL SUPERELEVATED SECTION
NOT TO SCALE





SR 0092 ALTERNATE SECTION
NOT TO SCALE

LGTS / Moment Slab with Toe Wall



Traffic Control During Construction



ANTICIPATED PROJECT SCHEDULE

FINAL DESIGN AND RIGHT-OF-WAY ACQUISITION: SUMMER/FALL 2020
CONSTRUCTION: 2021

NOTE:

1. VARIABLE MESSAGE SIGNS WILL BE UTILIZED TO ALERT THE PUBLIC OF THE CLOSURE DATE AT LEAST TWO WEEKS IN ADVANCE.
2. SIGNAGE ALONG DETOUR ROUTE NOT SHOWN. LAYOUT WILL MEET GUIDELINES SET FORTH IN PENNDOT PUBLICATION 213 (TEMPORARY TRAFFIC CONTROL GUIDELINES).

LEGEND:

	CAR DETOUR ROUTE (TOTAL LENGTH = 13.3 MILES)
	TRUCK DETOUR ROUTE (TOTAL LENGTH = 29.0 MILES)
	PROJECT AREA
	STATE OR U.S. ROUTE
	EXISTING RAILROAD
	EXISTING TOWNSHIP ROADWAY
	EXISTING LOCAL ROADWAY
	COUNTY AND MUNICIPAL BOUNDARY

- 13.3 Mile Posted Detour Route cars, 29.0 mile posted detour trucks on all state roads, limited crossings of the river, expedite construction Mid-May to Mid-October
- Local road review
- Work area to include entire roadway footprint

Preliminary Engineering Milestones:

- Line, Grade, and Typical Section Approval – October 2019
- SHPO Concurrence of Section 106 No Adverse Effect – March 2020
- Township/School District/Emergency Services Coordination Complete & Detour Accepted – March 2020
- March 11, 2020 Covid19 Restrictions in place
- BRPA Environmental Document Approved - April 2020
- Safety Review Approval of Proposed Design – May 2020

Structure Condition of High Concern Must Keep the Project Moving Forward


- No public meetings due to Covid19
- Final Design begins June 2020
- Anticipated Letting March 2021, 1 construction season, no apparent public controversy

Inspection September 2020 – Weight Posting 20T:


- Now on a 6 month inspection cycle need to get to construction ASAP
- Added a Priority 2 for footing underpinning.

- Fall 2020 pre-final PS&E, constructability review, and most design approvals in place
- **But** what about the public involvement put on hold by Covid19? Still no public interaction allowed due to Covid. District requires public review due to detour.
- Did a 2 week display of the plan and project info to receive feedback – late October 2020.
- Local representatives at County and State levels contacted by business owners
- pandemic along with excessive detour would severely impact local businesses
- Need to find a way to maintain traffic and still meet the environmental commitments
- Planned construction advertisement – 3 months away


New MPT - Staged Single Lane with Soil Nail Wall



ADVANCE SIGNING NORTHBOUND





SR 0092
LOOKING NORTHBOUND
STAGE 2
NOT TO SCALE



STAGE 2 - PLAN

Stage 1 Construction - Temporary Widening



TEMPORARY PREFABRICATED MODULAR WALL
FOR TRAFFIC CONTROL
(ITEM 9000-0010)

NOT TO SCALE

Railroad Provided Existing Structure Plan




LEHIGH VALLEY
SENECA DIVISION
DETAIL
OF
12' STONE ARCH
NO. 2
0.18 MILES W
WHITE'S FE
SCALE: AS SHOWN
OFFICE OF DIVISION EN
REVISED 6-11-28



Finally in Construction



Temporary Arch Support




Adequate hydraulic opening is to be maintained in temporary arch centering system where constructed in waterway for duration of construction. Do not block more than 25% of the span's hydraulic opening with temporary arch centering system. Remove daily and satisfactorily dispose of all debris, logs, ice, etc. that blocks the channel opening while temporary arch support system is in place at no additional cost to the Department.

Temporary Arch Support



Soil Nail Wall



SOIL NAIL ELEVATION - 1




Soil Nail Wall



Soil Nail Wall








Marking and Disassembly





Foundation Stabilization



FOUNDATION STABILIZATION SLAB ELEVATION - INLET

(LOOKING DOWNSTREAM)


2 0 2 4 FEET




Rebuilding




Rebuilding



GRS / Toe Wall / Moment Slab



GRS / Toe Wall / Moment Slab



**GEOSYNTHETIC REINFORCED SOIL (GRS) SLOPE
TYPICAL SECTION - WITHIN LIMITS OF WINGWALL**


NOT TO SCALE

Δ SEE ROADWAY PLAN FOR VARYING CROSS SLOPES.


GRS / Toe Wall / Moment Slab



Concrete Floor



SECTION C-C
NOT TO SCALE



SECTION B-B
NOT TO SCALE

Existing Structure 2018 vs Final Construction



Engineering Estimate: \$2,086,610

vs bid \$1,558,286 (low bid) successful contractor T. Brennan Heavy Equipment LLC

Highest Bid of 5 bidders - \$2,422,222

Change Orders: \$20,005

Total final cost: \$1,578,291

2% Minority Participation

T. Brennan Heavy Equipment LLC performed 98% of the work

